



Hwy "J" Reconstruction

4/5/2016

2016 Project Cost:

Planning, Design, and Engineering	\$120,000
Construction	\$3,290,000
Total:	\$3,410,000

2016 Project Timeline:

Start	4/18/2016
Remove Pavement	4/20/2016
Widening Roadway	5/1/2016
Base Aggregate	7/5/2016
Base Asphalt	8/21/2016
Final Asphalt	9/5/2016
Painting/Marking	9/26/2016
Completion	11/5/2016

Project Manager

Sean Heaslip
Construction Superintendent
920-674-7265

1425 S Wisconsin Dr.
Jefferson, WI 53549

Hwy J CTH G to Collins Road

PROJECT UPDATES:

*****This section updates weekly*****

Description and Justification:

- ◆ Pavement Rating: 3 (out of 10)
- ◆ The existing two-lane roadway will have 4-inches of new asphalt placed
- ◆ The road will be closed to thru traffic—reduced to local access only
- ◆ The project will be completed by the Jefferson County Highway Department
- ◆ Expected to begin in April 2016



Hwy J existing pavement conditions, approaching STH 26 bridge headed West along Highway J

In the photo you can see cracking as a result of insufficient base aggregate and poor drainage, ruts formed in the wheel paths of vehicle travel, and crumbling at the road edges as a result of shoulder material washing away.

The project intends to improve site drainage, pavement conditions, increase visibility, and reduce curvature in roadway, and includes the removal of a hill which obstructs vision near CTH "W"